
							SITE NA CITY COUN	Y		
REV	DATE	MODIFICATION	IS				coon			
01 - Cover Sheet 02 - Equipment Layout 03 - Floor-Electrical Layout 04 - Structural Details 05 - Power Requirements-Power Distribution 06 - Environment - Delivery 07 - Equipment Dimensions 08 - HVAC - Interconnections 09 - Disclaimer - Site Readiness			GE Contact Name Phone Number Email Address							
						D NM 615 TYPICAL	TABLE FR	EE		
A mai	A mandatory component of this drawing set is the GE HealthCare Pre Installation manual. Failure to reference the Pre Installation manual will result in			Draw	/n by	Verified by	Concession	GON/Quote	PIM Manual	Rev
	incomplete documentation required for site design and preparation. Pre Installation documents for GE HealthCare products can be accessed on the web at: https://www.gehealthcare.com/support/manuals		www.gehealthcare.com/support/manuals		-	-	-	-	5483120-1EN	5
GE Hea the cor	GE HealthCare does not take responsibility for any damages resulting from changes on drawings made by others. Errors may occur by not referring to the complete set of final issue drawings. GE HealthCare cannot accept responsibility for any damage due to the partial use of GE HealthCare final issue drawings, however caused. All dimensions are in millimeters unless otherwise specified. Do not scale from printed pdf files. GE HealthCare accepts no			Format	Scale		File Name		Date	Sheet
urawin	s, nowever caused. All	responsibility or liability for defective work due to scaling from the	nom printed por mes. GE HealthCare accepts no	A3	1:50	FNLNI IC-TVP-BR	RIVO_NM_615_TA	ABLE FREE DWG	06/JUN/2025	01/10

EC		
DE	ITEM	
GANTRY	1	
COLLIMATOR CART (WITH	2	
MAIN DISCONNECT PANE	3	
INJECTOR CONTROL	4	
INJECTOR ON PEDESTAL	5	
ECG MONITOR	6	
XELERIS WORKSTATION (	7	
NM AQUISITION STATION	8	
L		
MATOR OPTIONS	COLLI	
LEHR COLLIMATOR (1 PER		
LEGP COLLIMATOR (1 PER		
MEGP COLLIMATOR (1 PE		
HEGP COLLIMATOR (1 PE		
ELEGP COLLIMATOR (1 PE		
WALL - ACCORDING TO R		
FINISHED FLOOR TO SLAB HEIGHT		
FALSE CEILING HEIGHT		



# **EQUIPMENT LAYOUT**


DESCRIPTION	DIMENSIONS LxWxH (mm)	WEIGHT (kg)
	2070x1530x2110	1595
/ITHOUT COLLIMATORS)	500x970x1458	68
ANEL (MDP)	146x406x610	23
	-	-
AL	-	-
	-	3
N (WITH TWO LCD MONITORS)	-	30
ION	445x169x386	11.3
	•	

PER SYSTEM/CART) - 62 kg
ER SYSTEM/CART) - 55 kg
PER SYSTEM/CART) - 103 kg
PER SYSTEM/CART) - 131 kg
PER SYSTEM/CART) - 62 kg

## TO RECEIVED DRAWING

-
min. 2.25 m

ITEM	QTY			
1		Gantry anchoring		
2		150x100 cable inle		
3		150x70 flush floor		
4		150x100 horizonta		
5		150x100 cable inle		
6		Main Disconnect I		
$\overline{\bullet}$	8	Electrical outlet 10		
	3	RJ 45 network soc		
01	1	System remote co indicator lamps re		
1	2	System emergence		
$\otimes$	1	System ON light (I		
$\overline{\mathbf{e}}$	1	Electrical outlet fo		
$\overline{\mathbf{c}}$	3	Electrical outlets f through a dedicat		
	1	RJ 45 network soc		
Flush floor duct				
	Wall	duct		



# **FLOOR-ELECTRICAL LAYOUT**

### DESCRIPTION

g (see Structural Details)

let on the floor

r duct

tal wall duct

let on the floor and 150x100 vertical duct from floor to MDP (h=1.1 m) Panel (MDP)

Basic system

10/16A 230V + G

ocket

control (Y), locked when power OFF "ON" and "OFF" impulse buttons with red=ON / green=OFF located at 1.50m above floor

cy off (SEO), (recommended height 1.50m-1.85m above floor)

(L) - 24V


Injector Option

for Injector: 230V 10/16A

Xeleris Option

for Xeleris workstation: 10/16A 230V + G linked to the hospital UPS or ted UPS of 1 kVA single phase (If available)

cket for Xeleris workstation



- Floor leveling area: 512 cm [201.6 in] x 374 cm [147.2 in] (covering the entire planned area of table and gantry surface).
- Slope less than 13 mm [0.5 in] over 4300 mm [160 in], if slope is between 13 mm [0.5 in] and 30 mm [1.18 in] refer to PIM for additional requirements.
- Flatness: the surface must be smooth, with ٠ deviations of no more than 5 mm [0.195 in] between depressions and high spots in any 1500 mm [59 in] throughout the room or system installation area.
- Floor surface: a single poured surface.
- Floor strength: in order to enable mounting of the system floor anchors, concrete floors must have a minimum cube strength of f'c=4350 psi. (30 MPa) at 28 days (curing time) for 25/30 concrete
- Floor thickness: the system's floor anchors ٠ are designed for use only on concrete floors that meet the minimal 140 mm [5.5 in] concrete floor requirements
- The selected anchoring method must have a pulling tensile force of 19.7 kN on each of the anchors bolting the NM gantry to the floor.

Rev Date: 15.Dec.21 WALL DUCT Dividers as required Removable coverplate per local code 

# **POWER REQUIREMENTS**

# **POWER DISTRIBUTION**

POWER SUPPLY	SINGLE PHASE (G+L+N) OR DUAL PHASE (G+L1+L2) 208-240 VAC ±10%
FREQUENCIES	50/60 Hz ± 3 Hz
MAXIMUM POWER DEMAND	6 kVA
CONTINUOUS (AVERAGE) POWER DEMAND	2.5 kVA

- Line supply should come into a Main Disconnect Panel (MDP) containing the protective units and controls. The section of the supply cable should be calculated in accordance with its length and the maximum permissible voltage drops, equal to 2.9% max. of regulation for feeder size.
- There must be discrimination between supply cable protective material at the beginning of the installation (main low-voltage transformer side) and the protective devices in the MDP.

## SUPPLY CHARACTERISTICS

- Power input must be separate from any others which may generate transients (elevators, air conditioning, radiology rooms equipped with high speed film changers ...)
- All equipment (lighting, power outlets, etc...) installed with GE system components must be powered separately.
- Phase imbalance 2% maximum.
- Maximum voltage regulation at full load= 6% (including line impedance)
- Transients must be less than 1500 V peak (on a 230 V line). A record of power input disturbances over a continuous one-week period (prior to delivery) enables determination of the frequency and degree of these disturbances and can be used to ascertain the need to provide line conditioning equipment.
- Inrush current can withstand up to 10 times the recommended circuit breaker rating that could be reached during system power up, due to the system main transformer.

## **GROUND SYSTEM**

Equipotential: The equipotential link will be by means of an equipotential bar. This equipotential bar should • be connected to the protective earth conductors in the ducts of the non GE cableways and to additional equipotential connections linking up all the conducting units in the rooms where GE system units are located.

## CABLES


- Power and cable installation must comply with the distribution diagram below. .
- All cables must be isolated and flexible, cable color codes must comply with standardsfor electrical installation.
- The cables from signaling and remote control (Y, SEO, L ...) will go to MDP with a pigtail length of 1.5 m, and will be connected during installation. Each conductor will be identified and isolated (screw connector).

## **CABLEWAYS**

The general rules for laying cableways should meet the conditions laid down in current standards and regulations, with regard to :

- Protecting cables against water (cableways should be waterproof)
- Protecting cables against abnormal temperatures (proximity to heating pipes or ducts)
- Protecting cables against temperature shocks
- Replacing cables (cableways should be large enough for cables to be replaced)
- Metal cableways should be grounded .





Notes :

3 x 10 mm<sup>2</sup> [8 AWG] cable with a usable length of 10 m [32.8 ft] is delivered with the system. If needed, a 19 m [62.3 ft] cable is available as a spare

GE gantry contains transformer with multiple taps that can accommodate listed voltages.

Table 1: GE Supplied MDP(A1) options				
System	Region	Ecat		
Brivo NM615, Discovery NM630, NM830	EU/EAGM	E45011CR/CL		
	USCAN LATAM	E4502SV (30A)		



05/10

## ENVIRONMENT

## ALTITUDE

Operating altitude: from -150 m [-492 ft] to 4100 m [13451 ft].

## MAGNETIC FIELD SPECIFICATIONS

In order to avoid interference on the system, the static field limits from the surrounding environment must be less than 1 Gauss in both the scan and the operator rooms.

## **VIBRATION SPECIFICATIONS**

The system components are sensitive to vibration in the frequency range of 0.5 to 20 Hz, depending on the amplitude of the vibration. It is the customer's responsibility to contract a vibration consultant or qualified engineer to verify that these specifications are met and implement an appropriate solution.

To minimize vibrations, the system must be installed on a solid floor, as far as possible from vibration sources (parking lots, roadways, heliports, elevators, hospital power plants... etc).

Please refer to the PIM for detailed information.

## **ACOUSTIC SPECIFICATIONS**

The system creates acoustic noise. In compliance with IEC 601-1-1standard the measured noise (at 1m distance away from the system) is less than 70 db.

It is recommended that the wall and ceiling surface is of a sound dampening material so that the noise is not reverberated and amplified.

## DELIVERY

### THE CUSTOMER/CONTRACTOR SHOULD:

- Provide an area adjacent to the installation site for delivery and unloading of the GEHC equipment.
- Ensure that the dimensions of all doors, corridors, ceiling heights are sufficient to accommodate the movement of GEHC equipment from the delivery area into the definitive installation room.
- Ensure that access routes for equipment will accommodate the weights of the equipment and any transportation, lifting and rigging equipment.
- Ensure that all necessary arrangements for stopping and unloading on public or private property not belonging to the customer have been made.

### DIMENSIONS OF DELIVERY WITH DOLLY TRANSPORT EQUIPMENT

EQUIPMENT	DIME	WEIGHT		
	LENGTH	1327 mm [52.2 in]		
NM GANTRY WITH DETECTORS	WIDTH	2213 mm [87.1 in]	1765 kg [3892 lb]	
	HEIGHT	2000 mm [78.75 in]		
	LENGTH	952 mm [37.5 in]		
NM GANTRY WITHOUT THE DETECTORS	WIDTH	2213 mm [87.1 in]	2175 kg [4685 lb]	
	HEIGHT	1950 mm [76.7 in]		

## **CONNECTIVITY REQUIREMENTS**

Your new GE Healthcare imaging modality will require local and remote connectivity to enable our full range of digital support:

- Local connectivity This allows your system to connect to local devices such as PACS and modality worklist. We will require network information to configure the system(s), and a live ethernet port(s) prior to the delivery of the system(s).
- Remote connectivity Your GE Healthcare service warranty includes InSite<sup>™</sup> (applicable to InSite capable products), a powerful broadband-based service which enables digital tools that can help guard your hospital against equipment downtime and revenue loss by quickly connecting you to a GE Healthcare expert.

Depending on product family and software version, imaging systems can be connected in one of the following methods:

- 1. TLS over TCP Port 443 (Preferred method for new products) via:
  - a. DNS resolution
  - b. Customer-provided Proxy or
  - c. GE Proxy (Available in some regions)
- 2. Site-to-Site IPsec VPN tunnel

Please provide the GE project manager with the contact information for the resource that can provide information required to set up these connections. GEHC will send out communication to these contacts, which will include the project's Connectivity requirements, and a Connectivity form. This form will need to be completed and returned to GEHC prior to delivery of the system to ensure the system is tested and connectivity is enabled prior to the completion of the installation.

## **RADIOACTIVE ISOTOPES**

### USING RADIOACTIVE ISOTOPES

Since the system involves the use of radioactive isotopes, compliance with Nuclear Regulatory Commission regulations, or similar regulatory requirements (depending on the country), must be adhered to and all permissions obtained well in advance. It is recommended that regulatory compliance is arranged early in the site planning process.


It is essential that all preparations are completed so that required source materials can be obtained prior to installation, including calibration sources. Take into consideration that these sources may have fairly long delivery lead times, yet may also have a short half life, so that it may not be advisable to store them over long periods of time.

## **RADIOACTIVE ISOTOPES FOR SYSTEM CALIBRATION**

DESCRIPTION				
Basic calibration	Site has license for Tc <sup>99m</sup> Tc <sup>99m</sup> will be available during installation			
	Co <sup>57</sup> (Rectangular Flood Source)			
	TI <sup>201</sup>			
Isotopes to be used at site are available for installation.	l <sup>131</sup>			
	123			
Note: Specify age and strength	In <sup>111</sup>			
	Ga <sup>67</sup>			
	Xe <sup>133</sup> (inhalation gas)			

**Environment - Delivery** 

06/10



## **TEMPERATURE AND HUMIDITY SPECIFICATIONS**

### **IN-USE CONDITIONS**

	EXAM /CONTROL ROOM			
	Min	Recommended	Max	
Temperature	18 °C [64 °F]	22 °C [72 °F]	26 °C [79 °F]	
Temperature gradient	≤ 3 °C/h [≤ 5 °F/h]			
Relative humidity (1)	30% to 60%			
Humidity gradient	≤ 5%/h			

## **STORAGE CONDITIONS**

Temperature	+4 °C to +27 °C [+40 °F to +80 °F]			
Temperature gradient	≤ 3 °C/h [≤ 5 °F/h]			
Relative humidity (1)	20% to 60%			
Humidity gradient	≤ 5%/h			
Air pressure	700 hPA to 1060 hPa			

(1) non condensing

## **AIR RENEWAL**


According to local standards.

### NOTE

In case of using air conditioning systems that have a risk of water leakage it is recommended not to install it above electric equipment or to take measures to protect the equipment from dropping water.

# **HEAT DISSIPATION**

ROOM	DESCRIPTION	HEAT DISSIPATION (kW)	HEAT DISSIPATION (BTU/hr)
		MAX	MAX
Exam Room	Gantry	1.00	3412
	TOTAL	1.00	3412
Exam/Control Room	NM acquisition station	0.08	256
	Xeleris Workstation	0.08	256
	TOTAL	0.15	512



## DISCLAIMER

# **CUSTOMER SITE READINESS REQUIREMENTS**

## **GENERAL SPECIFICATIONS**

- GE is not responsible for the installation of developers and associated equipment, lighting, cassette trays and protective screens or derivatives not mentioned in the order.
- The final study contains recommendations for the location of GE equipment and associated devices, electrical wiring and room arrangements. When preparing the study, every effort has been made to consider every aspect of the actual equipment expected to be installed.
- The layout of the equipment offered by GE, the dimensions given for the premises, the details provided for the pre-installation work and electrical power supply are given according to the information noted during on-site study and the wishes expressed by the customer.
- The room dimensions used to create the equipment layout may originate from a previous layout and may not be accurate as they may not have been verified on site. GE cannot take any responsibility for errors due to lack of information.
- Dimensions apply to finished surfaces of the room.
- Actual configuration may differ from options presented in some typical views or tables.
- If this set of final drawings has been approved by the customer, any subsequent modification of the site must be subject to further investigation by GE about the feasibility of installing the equipment. Any reservations must be noted.
- The equipment layout indicates the placement and interconnection of the indicated equipment components. There may be local requirements that could impact the placement of these components. It remains the customer's responsibility to ensure that the site and final equipment placement complies with all applicable local requirements.
- All work required to install GE equipment must be carried out in compliance with the building regulations and the safety standards of legal force in the country concerned.
- These drawings are not to be used for actual construction purposes. The company cannot take responsibility for any damage resulting therefrom.

## CUSTOMER RESPONSIBILITIES

- It is the responsibility of the customer to prepare the site in accordance with the specifications stated in the final study. A detailed site readiness checklist is provided by GE. It is the responsibility of the customer to ensure all requirements are fulfilled and that the site conforms to all specifications defined in the checklist and final study. The GE Project Manager of Installation (PMI) will work in cooperation with the customer to follow up and ensure that actions in the checklist are complete, and if necessary, will aid in the rescheduling of the delivery and installation date.
- Prior to installation, a structural engineer of record must ensure that the floor and ceiling is designed in such a way that the loads of the installed system can be securely borne and transferred. The layout of additional structural elements, dimensioning and the selection of appropriate installation methods are the sole responsibility of the structural engineer. Execution of load bearing structures supporting equipment on the ceiling, floor or walls are the customer's responsibility.

## **RADIO-PROTECTION**

Suitable radiological protection must be determined by a qualified radiological physicist in conformation with local regulations. GE does not take responsibility for the specification or provision of radio-protection.

THE UNDERSIGNED, HEREBY CERTIFIES THAT I HAVE READ AND APPROVED THE PLANS IN THIS DOCUMENT.				
DATE	NAME	SIGNATURE		

## **REQUIRED MANUALS FOR SYSTEM PRE-INSTALLATION**

Description	
Product specific Pre-installation Manual	
*decuments can be accessed in multiple languages a	+ http

- A mandatory component of this drawing set is the GE HealthCare Pre-installation manual. Failure to reference the Pre-installation manual will result in incomplete documentation required for site design and preparation.
- The items on the GE HealthCare Site Readiness Checklist DOC2949061 and Worksheet DOC2949068 are REQUIRED to facilitate equipment delivery to the site. Equipment will not be delivered if these requirements are not satisfied.
  - Any deviation from these drawings must be communicated in writing to and reviewed by your local GE • HealthCare installation project manager prior to making changes.
  - Make arrangements for any rigging, special handling, or facility modifications that must be made to ٠ deliver the equipment to the installation site. If desired, your local GE HealthCare installation project manager can supply a reference list of rigging contractors.
  - New construction requires the following;
    - Secure area for equipment, 1.
    - 2. Power for drills and other test equipment,
    - 3. Restrooms.
  - Provide for refuse removal and disposal (e.g. crates, cartons, packing) ٠
  - It is required to minimize vibrations within the scan room. It is the customer's responsibility to contract a vibration consultant/engineer to implement site design modifications to meet the GE vibration specification. Refer to the system Pre-installation manual for vibration specifications.

**Document Number\*** 

Refer to cover page

documents can be accessed in multiple languages at https://www.gehealthcare.com/support/manuals