

# POWER SPECIFICATIONS

## Discovery ST

(REV. DATE 03/18/08)

**VOLTAGE**

PRIMARY SOURCE IS REQUIRED FOR ALL INSTALLATIONS.  
 RANGE OF LINE VOLTAGES: NOMINAL LINE VOLTAGE OF 380 TO 480, 3 PHASE, 50 OR 60 Hz.

REQUIRED POWER SUPPLY: WYE CONNECTED.

MAXIMUM DAILY VOLTAGE VARIATION MUST FALL WITHIN ONE OF THE RANGES IN TABLE A.

**TABLE A  
 ALLOWABLE  
 INPUT  
 VOLTAGES/  
 CURRENT  
 DEMAND**

NOMINAL VOLTAGE	ABSOLUTE RANGE	CURRENT (AMPS)		MINIMUM STANDARD OVERCURRENT PROTECTION
		MOMENTARY	CONTINUOUS	
380	350-410	137	30	110-A
400	368-432	130	29	110-A
420	386-454	124	27	110-A
440	405-475	118	26	110-A
460	423-497	113	25	110-A
<b>480</b>	<b>442-518</b>	<b>108</b>	<b>24</b>	<b>110-A</b>

(ALL CALCULATIONS BASED UPON NOMINAL VOLTAGE)

**PHASE-BALANCE.**

PHASE-TO-PHASE VOLTAGES MUST BE WITHIN ±2 PERCENT OF THE LOWEST PHASE-TO-PHASE VOLTAGE. MAXIMUM ALLOWABLE TRANSIENT VOLTAGE EXCURSIONS ARE 2.5 PERCENT OF RATED LINE VOLTAGE AT A MAXIMUM DURATION OF 1 CYCLE AND FREQUENCY OF 10 TIMES PER HOUR.

VOLTAGE TRANSIENT OR IMPULSE ON THE INCOMING POWER MUST BE HELD TO A MINIMUM. TRANSIENTS CAUSED BY LIGHTNING, SURGES, LOAD SWITCHING, STATIC ELECTRICITY ETC. CAN CAUSE SCAN ABORTS OR, IN EXTREME INSTANCES, COMPONENT FAILURE IN THE COMPUTER SUBSYSTEM.

**POWER DEMAND**

CONTINUOUS POWER DEMAND = 34 KVA (MAX DEMAND = 90 KVA)

**TABLE B  
 MAXIMUM  
 MOMENTARY  
 POWER  
 DEMAND.**

DEMAND	Discovery ST
kVa *	90
POWER FACTOR AT	0.85

\* DEMAND INCLUDES POWER FOR ENTIRE CT SYSTEM. LINE VOLTAGE REGULATION AT MAXIMUM POWER DEMAND MUST BE LESS THAN OR EQUAL TO 6 PERCENT.

**DISTRIBUTION TRANSFORMER**

FOR A SINGLE UNIT INSTALLATION, THE MINIMUM TRANSFORMER SIZE IS 112.5 KVA. GE DOES NOT RECOMMEND USING A REGULATION DEVICE.

NOTE: THE CT SYSTEM MUST NOT BE POWERED IN A MULTIPLE INSTALLATION WHERE FILM CHANGERS ARE USED. FILM CHANGERS UTILIZE A LARGE NUMBER OF HIGH POWERED CLOSELY SPACED EXPOSURES WHICH MAY COINCIDE WITH THE CT SCAN.



## FEEDER TABLE

### FEEDER TABLE – DISCOVERY ST

REV. DATE: 12.Apr.11

- CALCULATIONS BASED UPON NOMINAL VOLTAGE, WIRE SIZE IN AWG.
- RECOMMENDED FEEDER SIZES FROM DISTRIBUTION TRANSFORMER TO THE POWER CABINET
- NEUTRAL MUST BE TERMINATED INSIDE THE MAIN DISCONNECT PANEL AND NOT AT ANY GE CABINET.
- THE GROUNDING CONDUCTOR ( ) WILL BE A 1/0 MINIMUM. THIS GROUND WILL RUN FROM THE EQUIPMENT BACK TO THE FACILITY POWER SOURCE/MAIN GROUNDING POINT AND ALWAYS TRAVEL IN THE SAME CONDUIT WITH THE FEEDERS AND NEUTRAL.
- \* MINIMUM SIZE FOR CIRCUIT BREAKER, NEC ARTICLE 517-73.
- FOR A FULL SYSTEM UPS, REFER TO ELECTRICAL DETAILS FOR UPS FEEDER WIRES.

RUN LENGTH IN FEET	POWER SUPPLY VOLTAGE											
	342-418 380		360-440 400		378-462 420		396-484 440		414-506 460		432-528 480	
	FEEDER	GROUND	FEEDER	GROUND	FEEDER	GROUND	FEEDER	GROUND	FEEDER	GROUND	FEEDER	GROUND
50	2	(1/0)	2	(1/0)	2	(1/0)	2	(1/0)	2	(1/0)	<b>2</b>	<b>(1/0)</b>
100	2	(1/0)	2	(1/0)	2	(1/0)	2	(1/0)	2	(1/0)	<b>2</b>	<b>(1/0)</b>
150	2	(1/0)	2	(1/0)	2	(1/0)	3	(1/0)	3	(1/0)	<b>3</b>	<b>(1/0)</b>
200	1	(1/0)	1	(1/0)	2	(1/0)	2	(1/0)	3	(1/0)	<b>3</b>	<b>(1/0)</b>
250	1/0	(1/0)	1	(1/0)	1	(1/0)	1	(1/0)	2	(1/0)	<b>2</b>	<b>(1/0)</b>
300	2/0	(1/0)	2/0	(1/0)	1/0	(1/0)	1	(1/0)	1	(1/0)	<b>1</b>	<b>(1/0)</b>
350	3/0	(1/0)	2/0	(1/0)	2/0	(1/0)	1/0	(1/0)	1/0	(1/0)	<b>1</b>	<b>(1/0)</b>
400	4/0	(1/0)	3/0	(1/0)	3/0	(1/0)	2/0	(1/0)	2/0	(1/0)	<b>1/0</b>	<b>(1/0)</b>